

Phone: (573) 426-2176 Fax: (573) 364-2930 E-mail: info@gatewaytubing.com GATEWAY TUBING, INC. P.O. Box 640 Rolla, Missouri 65402



FACTORY MUTUAL TESTING OF SIDEWINDER™ SPRINKLER DROPS

Sidewinder[™] sprinkler drops are FM approved under Factory Mutual Standard 1637, and have passed all tests for Factory Mutual approval and certification. The tests include the following:

• <u>Fatigue</u>

SidewinderTM flexible hoses were bent in a "J" shape, and then filled with water to a pressure of 175 psi. Each hose was then flexed through a travel of 8" a total of 50,000 cycles. The samples were then pressurized with water to 70 psi for 5 minutes. *Results*: No leaks occurred.

Vibration

SidewinderTM flexible hoses were mounted in mock suspended ceilings which were in turn attached to a vibration table. Each flexible hose was filled with water and pressurized to 90 psi. The assembly was then subjected to a series of vibrations for a period of 25 hours for a total of over $\underline{2.4 \text{ million vibrations}}$. The vibrations ranged from 18 vibrations per second to 37 vibrations per second. After the vibration testing was completed, each hose was hydrostatically pressurized to 700 psi for 5 minutes. *Results*: No leaks occurred.

• Pressure Cycling.

SidewinderTM drops were subjected to <u>20,000 cycles</u> of pressure varying from 0 psi to 175 psi. The samples were tested in both a straight position and in a 90° bent position. After completing the 20,000 cycles, the models were hydrostatically pressurized to 700 psi, with the pressure sustained for 5 minutes. *Results*: <u>No leaks occurred</u>.

Vacuum

Sidewinder[™] flexible drops were subjected to a vacuum of 25" mercury for a period of 5 minutes. Afterwards, each sample was hydrostatically pressurized to 700 psi, with the pressure sustained for a period of 5 minutes. *Results*: No leaks occurred.

• High Pressure Flow

Flow tests were conducted on SidewinderTM flexible drops in order to test for rigidity of the mounting assembly. SidewinderTM drops were mounted in a commercial T-bar suspended ceiling, with standard response automatic sprinklers installed in the sprinkler drops. Multiple tests were conducted at high flow with pressures ranging from 25 psi through 175 psi. *Results*: Each mounting assembly remained in place and functional.

